

# Instructions

# Chrysler 42RE, 42RH, A904



Part	No.	
12780-Z		


• Shims (10)

.010" thick

NOTE: For 3- or 4-tanged OE washers.

#### Shim Specifications:

Material: Steel Inner Dia.: 2.000" Thickness: 0.010" Outer Dia.: 2.810"



### **1. Inspection**

- a. Inspect rear annulus gear and shaft. If wear is visible Sonnax **12780-Z** shim(s) are generally required to reduce gear train endplay.
- b. Measure endplay of planetary, sun gear, and driving shell as an assembled unit. Stand assembly upright, with the snap ring installed, on a flat surface.
- c. Pull upward on output shaft and measure clearance by inserting a feeler gauge between the rear annulus gear support hub and the output shaft shoulder. Factory specification for this clearance should be between .005–.048". A minimum of .005–.010" endplay is preferred.
- d. If the clearance exceeds these specifications, install Sonnax shim(s).

## 2. Installation

Insert shim(s) between the #9 thrust washer and rear planet assembly.

